

Services in Masonry / Partition Walls

To facilitate this ambition of getting the quality right, these checks should take place:

- Ensure a void closure document is signed off prior to covering up services
- Ensure back-to-back chases and service installations are avoided where possible as these may reduce acoustic integrity
- Are acoustic putty pads required to electrical back boxes?
- Avoid inaccessible joints on piped services
- Protect services to be cast in and allow for movement
- Ensure the services are tested before being covered up
- Record dimensioned routes on 'as built' drawings

Our Quality vision:

We will get it right first time on all our projects by delivering exceptional customer service

